

Ensure to level the tray on

all outer edges.

Lay the tray in position, push against the

wall and bed down onto the mortar screed


Ensure all of the base is supported by the

cement. Level the tray from each edge

Leave for 24 hours prior to next step.

Apply a bead of silicone along the centre of each edge of the tray to be

fitted against the wall(s).



5

24 HOURS

**DRYING TIME** 

